



LOCATION

Jessup, PA

DATE OF WORK

March 2017

PROJECT

B-10431

Transformer from
of entry to foundation



HLL railed this 458,828 lb unit from Laredo, TX to a rail siding in Jessup, PA. After arriving at the rail siding, the transformer had to be offloaded from its heavy-duty rail car to an over the road transport system to be delivered to the substation. The best choice for offloading this heavy transformer from the rail car and loading to the large transporter was using a jack and slide system. The crew jacked the transformer up off of the car, and used the slides to move the unit over to the platform trailer.

Once loaded to the transport trailer, the transformer had a long haul to the final destination inside the substation. After the safe arrival it was removed from the transporter using the jack and slide system again. Then it was placed onto a turntable and rotated to its final orientation and set in the customers center marks. Accessories were delivered and placed next to the pad.