



LOCATION

Latimer, IA

DATE OF WORK

March 2019

PROJECT

B-13377

*Transformer from port of entry to foundation*

HLL railed this 195,032 lb. unit from Laredo, TX to a rail siding in Garner, IA. After arriving at the rail siding, the transformer had to be offloaded from its heavy duty rail car to an over the road transport system to be delivered to the substation. The best choice for offloading this heavy transformer from the rail car and loading the Goldhofer transporter was using a jack and slide system. The crew jacked the transformer up off of the car, and used the slides to move the unit over to the Goldhofer trailer.

Once loaded to the road transporter, the transformer was hauled to the final destination inside the substation. After a safe arrival at the substation location, it was removed from the transporter using the jack and slide system again. This put the transformer onto the final pad and it was ready for assembly and installation. Job was completed on time and on budget.

