



LOCATION

Mobile, AL

DATE OF WORK

December 2021

PROJECT

B-15069

*Yankee Dryer from port of entry to storage.*



This 237,486 Lbs. Yankee Dryer was shipped via ocean freight from the manufacturer in Karlstad, Sweden via Antwerp to Port Mobile, AL. The Yankee arrived at Port Mobile, AL in a heavy lift ship. With the securements cut loose from the unit, it was lifted out of the ship's cargo hold and placed onto the awaiting barge crane. The barge was then moved North to Pier C, where a dual lane trailer was staged. The Yankee was now lifted from the barge and secured to the trailer for transportation to the site.



Early next morning the Yankee was moved outside of the port to a staging area, where it sat until 8pm. The move was carried out in the evening to minimize disruptions to traffic. At 8:20pm it began its slow and meticulous haul to the customers site. Around 9:30pm it arrived at its destination. Unloading occurred the following afternoon. HLL's team positioned a smaller SPMT (Goldhofer) and beams adjacent to the trailer and skid the cargo from trailer to the SPMT. Yankee was then jacked-up to remove the skid tracks, then it was jacked down to transport beams. Now it was ready to be transported to the clients pedestals inside the storage facility. Once positioned correctly above the pedestals, the Yankee was lowered and secured onto the pedestals. Crew demobilized from site.

